SDAB2018-0141

1 A101 MAIN FLOOR PLAN - ~~DEMOLITION~~ Proposed 1 : 50

2 A101 REFLECTED CEILING PLAN - DEMOLITION 1 : 50

LEGEND: EXISTING MATERIALS

- FLUORESCENT LIGHT FIXTURE
- 610mm X 1220mm LAY-IN-TILE CEILING
- CEILING MOUNTED DIFFUSER
- RECESSED POT LIGHT FIXTURE IN GYPSUM BOARD CEILING
- OPEN WEB STEEL JOIST - @ ROOF LEVEL
- WINDOW/DOOR HEAD
- LINE OF EXISTING PARTY WALL ASSEMBLY

DEMOLITION KEYNOTES: SHOWN AS (1) THUS

1. REMOVE EXISTING LAMINATE FLOORING, PREP FLOOR FOR NEW FLOORING MATERIAL - SEE SHEET A102 FOR DETAILS
2. REMOVE EXISTING CERAMIC FLOORING, PREP FLOOR FOR NEW FLOORING MATERIAL - SEE SHEET A102 FOR DETAILS
3. REMOVE EXISTING STUD WALL FRAMING - PATCH AND MAKE GOOD ALL SURFACES AFFECTED
4. REMOVE EXISTING CLEAR GLASS FRAMING SYSTEM - PATCH AND MAKE GOOD ALL SURFACES AFFECTED
5. REMOVE EXISTING STUD WALL FRAMING PORTION SUSPENDING BELOW 2ND FLOOR - PATCH AND MAKE GOOD ALL SURFACES AFFECTED - PREP AREA FOR NEW FULL HT WALL ASSEMBLY - SEE A102 FOR DETAILS
6. REMOVE EXISTING POT LIGHTING FIXTURES, GYPSUM BOARD CEILING, STEEL STUD FRAMING, INTERIOR GLASS SKYLIGHT - ALL CEILING AND ITEMS TO BE REMOVED.
7. EXISTING LAY-IN-TILE CEILING AND TILES TO BE PROTECTED DURING DEMOLITION OF STUD FRAMING REMOVAL - CONTRACTOR TO COORDINATE EFFORTS WITH OWNER

PROJECT: DISPENSARY

1711 52 STREET S.E.
Calgary, Alberta

DRAWING TITLE: DEMOLITION PLANS

DATE STARTED: 30_03_2015
SCALE: AS NOTED
PROJECT NUMBER:
DRAWN BY: CTM
CHECKED BY: PM

A101